



Plant Schedule						
GRASSES/HERBACEOUS PLANTS						
Abb	Species	Size	Height (cm)	Density	Area	Number
CKF	Calamagrostis 'Karl Foerster'	5L	40-50	4	sq.m	60
CmE	Carex oshimensis 'Evergold'	5L	20-30	5	sq.m	20
CbRR	Carex buchananii 'Red Rooster'	5L	20-30	5	sq.m	55
Fg	Festuca glauca 'Elijah Blue'	5L	20-30	5	sq.m	97
HmA	Hakonechloa macra 'Aureola'	5L	20-30	5	sq.m	95
HMB	Helenium 'Moerheim Beauty'	5L	30-40	4	sq.m	38
HC	Heuchera 'Caramel'	5L	20-30	5	sq.m	83
HPP	Heuchera 'Palace Purple'	5L	20-30	5	sq.m	80
LaV	Lavandula angustifolia 'Vera'	5L	30-40	5	sq.m	15
MsG	Miscanthus sinensis 'Gracillimus'	5L	40-50	4	sq.m	44
RFg	Rudbeckia fulgida 'Goldstrum'	5L	30-40	6	sq.m	52
St	Stipa tenuissima	5L	30-40	5	sq.m	62
SHRUBS						
Abb	Species	Size	Height (cm)	Density	Area	Number
Aml	Amelanchier lamarkii (multi-stem)	20L	150-200	/	Ind	7
CaS	Cornus alba 'Sibirica'	3L	100-120	3	sq.m	12
CsWG	Cornus sericea 'White Gold'	3L	100-120	3	sq.m	24
CRP	Cotinus 'Royal Purple'	20L	100-120	/	Ind	20
HEG	Hebe 'Emerald Green'	5L	20-30	5	sq.m	70
Hq	Hydrangea quercifolia	5L	40-50	4	sq.m	133
PS	Phormium 'Sundowner'	20L	80-120	/	Ind	6
PJ	Phormium 'Jester'	20L	80-120	/	Ind	14
PmM	Pinus mugo 'Mops'	5L	30-40	5	sq.m	200
Pv	Pleioblastus variegatus	5L	30-40	4	sq.m	60
HEDGE						
Abb	Species	Size	Height (cm)	Density	Area	Number
Plu	Prunus lusitanica	5L	40-60	4	lin.m	120
TREES						
Abb	Species	Girth	Height (cm)	Type	Area	Number
Bj	Betula utilis var. jaquemontii		300-400	Multi-stem	Ind	4
CcFP	Cercis canadensis 'Forest Pansy'		300-400	Multi-stem	Ind	2
Ck	Cornus kousa		300-400	Multi-stem	Ind	1
MdWP	Malus domestica 'Worcester Pearmain' (Apple MM106 rootstock)	8-10	250-350	Standard	Ind	2
PcC	Pyrus communis 'Conference' (Quince C rootstock)	8-10	250-350	Standard	Ind	2

KEY

Proposed feature multi-stem small tree/ large shrub on the podium deck to be planted as 200-300mm high specimens, secured with wire ground anchors which should be fixed to the inside of the planters.

Proposed fruit tree to be grafted on a small growing root stock, trees to be planted as 8-10cm standards secured with wire ground anchors which should be fixed to the inside of the planters.

Proposed planting beds to be planted as 3L- 5L shrubs planted as shown with occasional 20L specimen's. All beds to be barked mulched with a small grade mulch material.

Proposed planting beds within the allotment area to be filled with topsoil and left empty free from any weeds ready for the residents to take ownership of.

Rev C - Scale bar added EP 24-08-17
Rev B - Updated inline with updated GA drawings and submitted for PLANNING EP 27-07-17
Rev A - Updated inline with GA drawings ready for tender ES 150617

DEP LANDSCAPE ARCHITECTURE LTD

BLACKFRIARS HOUSE, PARSONAGE
MANCHESTER, M3 2JA
T: 0161 2419878
E: info@dep.co.uk
W: www.dep.co.uk

Client
Beaumont Morgan Developments Ltd

Project
Ordsall Lane, Salford

Description
Planting Plan - Plaza

Drawn
1:200@A1
Job number
3206

ES Chkd EP
Date
06/16
Revision
C

Copyright DEP Landscape Architecture Ltd

All levels and dimensions to be checked on site by contractor prior to commencement; Any variations to be reported to the client. This drawing is to be read in conjunction with all others relating to the project and all information derived accordingly; any anomalies to be reported to the client. Do not scale from this drawing. Use figured dimensions only. Work shown on this drawings to be carried out in accordance with current British Standards and Codes of Practice.

© Copyright to DEP Landscape Architecture Limited. The information shown on this drawing shall not be reproduced or copied in any form without prior written consent from DEP Landscape Architecture Limited.

- PLANTING NOTES:
1. Plant handling at the nursery, and during transit up to delivery, shall be in accordance with 'Plant Handling', the booklet published by the Committee for Plant Supply and Establishment (CPSE). The contractor shall comply with clauses 3 & 4 of the above booklet (obtained from the Horticulture Trades Association, 19 High Street, Theale, Reading, Berks RG7 5H) which refers to the receipt, unloading and temporary storage of plants.

2. Plants shall be first class examples of their species or variety, free from all pests and diseases, with good fibrous root systems and materially undamaged (refer to relevant sections of BS3936 Parts 1-4 'Specification of Nursery Stock').

3. All planting is to be in general compliance with BS4428: 1989 'Code of Practice for general landscape operations (excluding hard surfaces)'.
4. All planters and planters to be filled with depth of 350-450mm good quality topsoil and have a free draining sub-base, beds should be cultivated prior to planting and be free from weeds or any stones/ rubble material greater than 50mm. All planters shall have a suitable slow release fertilizer applied at the manufacturers specified rates.

5. All trees are to be staked and secured as follows:
Multi-stemmed trees within the planters are to be secured with underground guy anchor Platipus RF2P Tree anchor (or similar approved) which is fixed to the base or sides of the planter as per engineers specification.

6. For the shrubs, grasses and herbaceous plants; incorporate a slow release fertiliser into the back fill material when planting.

7. The contractor must ascertain for himself/herself the exact location of services and ducts prior to digging and planting.

8. All areas of planting within the planters are to be mulched to a depth of 50mm with small grade bark mulch for weed control in these areas.

9. Water all plants, trees and grass on the same day of planting and there after as necessary (min once a week during the summer in the first year establishment period) to ensure the establishment of the plants during the 12 months defects period. All beds to kept weed free.